

HTT Flooring - Hydrocore - Timber Flooring 1 of 2 Sample - Wet SlipTest
 SN240424-16

29 Apr 2024

Slip Resistance Classification of New Pedestrian Surfaces - AS4586:2013

This Test Report Is In Accordance with Appendix A	Wet Pendulum Test
Date Tested:	24 Apr 2024
Test Report Number:	SN240424-16
Client Name & Billing Address:	HTT Flooring Pty Ltd - Unit 2, 8 Gunya Street Regents Park NSW 2143
Project Name or Test Location:	SlipTest Australia NSW Headquarters - 5 Joynton Ave, Zetland NSW 2017
Surface Tested :	Hydrocore - Timber Flooring 1 of 2 Sample
Wet Pendulum Test carried out using :	Slider 96 (4S) Rubber slider
Any Variations to Standards	N/A
Testing Officer / Approved Signatory:	Shenea Neill
Pendulum in use - Calibration Date :	#1133 - Munro-Stanley Portable Skid Tester - (C: 13.10.23 - EN 13036-4)

Signature of Approved Signatory :



Test Results : (Samples and Test Information Supplied by Client)

Sample No.	Swing 1	Swing 2	Swing 3	Swing 4	Swing 5	Mean BPN	SCV :	Surface Picture
Spotted Gum	31	31	29	29	29	29	N/A	
Spotted Gum	30	30	29	29	29	29	N/A	

Sample No.	Swing 1	Swing 2	Swing 3	Swing 4	Swing 5	Mean BPN	SCV :	Surface Picture
Cafe Noir	34	31	31	30	30	30	N/A	
Ginger Ale	33	32	32	31	31	31	N/A	
Fire Wood	25	25	25	25	25	25	N/A	

Reported SRV For Test Area : 29

CLASSIFICATION using Slider 96 (4S Slider) P2 = 25 - 34

Accredited for Compliance with ISO/IEC 17025. The information presented herein and on the Sliptest Report is copyright and is protected by copyright law, any reproduction of this information and test report except in full is prohibited. Sliptest Australia Pty. Ltd. performed this on site test with reference to the following Australian Standard testing criteria, of AS 4586:2013 Classification of new pedestrian surface materials. Appendix A - Wet Pendulum Test Method and Hand Book HB 198: 2014 with reference to AS/NZS 4663: 2004 Slip Resistance measurement of existing pedestrian surfaces and HB 197: 1999. These results to not account for Future Wear, Maintenance or Contamination of this surface once in-situ.

Page 1 of 1 - END OF REPORT